

RIG #1 INVENTORY

DRAWWORKS:

Brewster N45 (700HP), Rated to 7,000' with 4½" Drill Pipe

MAST & SUBSTRUCTURE:

L.C. Moore - 97FT 315,000# SHL, 11FT Box on Box Substructure

POWER:

2 Caterpillar 3406 Engines, 350HP each @ 1800 RPM

PUMP #1:

Maxum 1000 (1000HP) Triplex Pump – Caterpillar 398 (1000HP)

PUMP #2:

Maxum 1000 (1000HP) Triplex Pump – Caterpillar 398 (1000HP)

ROTATING & TRAVELING EQUIPMENT:

Rotary Table – 17"

150 Ton Block/Hook Combo, 120 Ton Swivel

ABB – Offshore Crown Block Saver

GENERATOR #1:

Caterpillar C-15 Engine, 350 KW Generator

GENERATOR #2:

Caterpillar C-15 Engine, 350 KW Generator

B.O.P.:

Shaffer Type 11" 5,000# Double Ram

Choke Manifold 3,000#

Closing Unit 4-Station, 120 Gallon

MUD SYSTEM:

700 Barrel 2-Pit Mud System w/100 Barrel Pre-mix Pit

1 Linear Shale Shaker

De-Silter 8-Cone

De-Sander 2-Cone

DRILL PIPE & DRILL COLLARS:

4½" & 5" G105 Drill Pipe - From Inventory as needed

6½" & 8" Drill Collars – From Inventory as needed

LOCATION SIZE:

